BRUHATH BANGALORE MAHANAGARA PALIKE,

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/RD/WORK_INDENT50377

NAME OF WORK: De-silting and Re-setting of drain and Re asphalting of roads to Chikkasandra Area in ward no 12 Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	CHIKKABOREGOWDA KARIGOWDA (CKG CONSTRUCTIONS PRIVATE LIMITED)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.with all lead and lift charges & as per direction of engineer incharge of work.	Cum	2471.49	214.41	Rupees Two Hundred Fourteen and Forty Paise Only
2	Lead and Lift charges for Exvated Earth including loading and unloading complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	2471.49	83.61	Rupees Eighty Three and Sixty Paise Only
3	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	7061.41	7.19	Rupees Seven and Eighteen Paise Only
4	Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	1412.28	2261.45	Rupees Two Thousand Two Hundred Sixty One and Forty Four Paise Only

CKG Constructions Pvt. Ltd.,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Sl. No	Description of work	Unit	Qty	CHIKKABORE KARIGOWDA CONSTRUCTIONS LIMITED Sl. No In Figures (Rs.)	In Words
5	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 0.90kg/sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour, HOM of machineries complete as per specifications.. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	7061.41	49.11	Rupees Forty Nine and Ten Paise Only
6	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 100/120 TPH capacity H.M.P. with sensor paver Gr-1 (50 mm to 75mm) with 3.3 % VG-30 Bitumen with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	353.07	8239.67	Rupees Eight Thousand Two Hundred Thirty Nine and Sixty Six Paise Only
7	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 0.90kg/sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour, HOM of machineries complete as per specifications.. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	7061.41	49.11	Rupees Forty Nine and Ten Paise Only

Managing Director

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Sl. No	Description of work	Unit	Qty	CHIKKABOREGOWDA KARIGOWDA (CKG CONSTRUCTIONS PRIVATE LIMITED)	
				In Figures (Rs.)	In Words (Rs.)
8	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 508 complete in all respects complete as per specifications. - using 100/120 TPH capacity H.M.P. with sensor paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumenwith all lead and lift charges & as per direction of engineer incharge of work.	Sqm	176.54	10614.90	Rupees Ten Thousand Six Hundred Fourteen and Ninety Paise Only
9	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	389.84	601.55	Rupees Six Hundred One and Fifty Five Paise Only

G Constructions Pvt. Ltd.

gnature of the Contractor,

Executive Engineer,
Dasarahalli Division,